



Rhif y Cais / Application Number: C16/1258/39/MG

Cynllun lleoliad ar gyfer adnabod y safle yn unig. Dim i raddfa. Location Plan for identification purposes only. Not to scale.





Ordnance Survey, (c) Crown Copyright 2016. All rights reserved. Licence number 100022432

Revisio			

Sean Caddick Architectural

13 Belvidere Walk Shrewsbury SY2 5LT

email: seancaddick@live.co.uk

Tel: 07971 166529

Client: Mr & Mrs R Oakes

Project:


Proposed Reserved Matters Application for Holiday Chalet and Parking Plot 21 Braich Farm Estate Mynytho Pwllheli

Drawing title: Location Plan

Scale: 1:1250 @ A4 Date:

September 2016

Drawing number: 16/1528/01 Revision:



Key

- - 1.m high timber close boarded fence

Native mixed hedge Crataegus, Prunus Spinosa And Acer Campestre 50%-25%-25% (common hawthorn) Density 5/lm

Tarmac road and footpath Surface 20mm thick 6mm aggregate Binding 40mm thick 20mm aggregate 200 mm thick sub-base MOT type 1

Gravel driveway

Riven paving slabs as approved sample

Grass

Grasscrete parking area

Sean Caddick Architectural

15.12.16

13 Belvidere Walk Shrewsbury SY2 5LT

email: seancaddick@live.co.uk

Tel: 07971 166529

Client:

Mr & Mrs R Oakes

Revision: A Parking added.

Project:

Proposed Reserved Matters Application for Holiday Chalet and Parking Plot 21 Braich Farm Estate Mynytho Pwllheli

Drawing title: Block Plan

Scale:

1:500 @ A3

September 2016

Date:

Drawing number: 16/1528/02

Revision:

Ordnance Survey, (c) Crawn Copyright 2016. All rights reserved. Licence number 100022432

PLANTING

All plants and planting to comply with the requirements of all current/relevant British Standard Specifications including BS 3936 Part 1 1992. Part 11 1990 and Part 1V 1984, where applicable BS 4428: 1989 and the Bali/Li/Nursery Trade tender Document (5th Edition: 1986) All plants to be supplied in accordance with the indicated schedule.

MAINTENANCE

Regular visits (minimum 12 No) required to maintain all planted areas in a weed and litter free condition using a combination of chemical spray and hand weeding to be agreed with the landscape Architect.

Maintenance to include watering, pruning pest and disease control and remulching as required. Grass mowing at 2 week intervals during growing season.

Structural planting areas shall be maintained as 'bare earth' non competitive weed free environment by repeated application of a glyphosate based herbicide. Persistant weeds and unwanted shrub shall be spot treated as necessary with an alternative herbicide to be agreed with the Landscape Architect.

Watering shall be carried out as described following any five day period without rain or as required by the Landscape Architect.

NB. Final visit to be immediately prior to handling over and include a fertiliser treatment of Enmag (6:20:10) at 100g/m2 and 25mm depth bark mulch top up to all planted areas.

FULL SPECIFICATION

Shall prevail in the event of any discrepancy with this summary.

NOTES REGARDING IMPLIMENTATION WORKS TO BE CARRIED OUT FTC

implementation timetables shall be the first planting season following completion of construction of the part of the site prior to occupation.

The works will be completed fully before occupation of any part of the development. Planting and trees shall remain as approved by Local Planning Authority for 5 years after approveddate and if damaged will be replaced with others of same species.

PLANT MATERIAL TREATMENT

Root Dip - Alignure Root Dip (1-3 solution) applied to all bare rooted stock (1) at time of lifting Nursery and

Anti-Desiccant - with proof \$800 to be applied to foliage of all containerised rootballed material in leaf, speciman conifers and evergreens etc. (1) prior to transportation and (2) during any delay planting.

New Hedge planting - New hedges are to be planted in two staggered rows, rows 300mm apart and plants within rows 400mm apart. Allow for 5 plants per linear metre. Plant in small single species groups to prevent competition between the species. Holly and larger growing trees are to be planted individually.

Immediately after planting cut hawthorn down to 150mm. If rabbits are a problem use shrub guards to protect plants, these are larger in diameter than spiral guards and so allow low lateral growth to develop. In the first spring after planting trim all lateral branches back by 50% (not holly). Prune damaged, diseased or dead wood immediately after first leaf break. Follow with a light trim every second or third year, allowing the hedge to increase in size each time. Replace dead, dying or damaged stock with the same species as soon as practicable in the first planting season following failure.

Check regularly that the shrub guards are sound and secure, and replace as necessary.

NB. All to be British Grown stock and fully hardend off. 0 (2) prior to planting. Pruning - Allow for Pruning of all deciduous shrubs by 1/3rd following planting at landscape architects direction in the Planting Schedule.

